Fire alarm drawing

13827-23714 APPROVED PLANS.pdf

SHEET NOTES

A. REFERENCE SHEET E000 FOR SYMBOLS, ABBREVIATIONS AND SHEET INDEX.

B. REFERENCE SHEET E002 FOR TECHNOLOGY SCOPE OF WORK.

C. COORDINATE WITH THE ARCHITECTURAL PLANS, ELEVATIONS, AND DETAILS THE LOCATIONS AND MOUNTING HEIGHTS OF ALL ELECTRICAL DEVICES PRIOR TO COMMENCING INSTALLATION.

D. EXISTING TO REMAIN, "EX", ON THIS PLAN REFERS TO THE STATUS OF BASIC ELECTRICAL DEVICES. THERE MAY BE SOME WORK REQUIRED IN THESE SPACES INVOLVING BACK-FEEDING EXISTING CIRCUITS OR OTHER MODIFICATIONS. SEE ALL DOCUMENTS THAT MAKE UP THIS CONTRACT FOR THE TOTAL EXTENT OF WORK REQUIRED IN ALL SPACES.

E. FIRE ALARM SYSTEM INDICATED ON THIS SHEET SHALL BE PROVIDED AND INSTALLED BY THE OWNER. E.C. SHALL PROVIDE ALL ROUGH-IN AND 120V ELECTRICAL CONNECTIONS, AS REQUIRED, FOR A COMPLETE AND OPERATIONAL SYSTEM. DEVICES INDICATED ON THIS SHEET WHICH DO NOT REQUIRE ROUGH-IN ARE SHOWN FOR PLACEMENT AND COORDINATION PURPOSES ONLY (IE: SMOKE DETECTORS, HEAT DETECTORS, FLOW AND TAMPER SWITCHES, CONTROL MODULES ECT.) REFERENCE E-002 AND E-560 FOR ADDITIONAL INFORMATION. CB1

F. PAGING SYSTEM AND ALL ASSOCIATED CABLING SHALL BE PROVIDED AND INSTALLED BY THE OWNER. PLACEMENT OF PAGING SYSTEM SPEAKERS ARE SHOWN FOR COORDINATION ONLY, UNLESS NOTED OTHERWISE.

G. EC SHALL PROVIDE ROUGH-IN REQUIREMENTS FOR THE OWNER PROVIDED AND INSTALLED ACCESS CONTROL SECURITY SYSTEMS AND WANDER MANAGEMENT SYSTEMS. REFERENCE SHEETS E-002, E-541 AND E-620 FOR ADDITIONAL INFORMATION.

H. NOT USED.

I. ALL PARTITION AND FLOOR PENETRATIONS SHALL BE SEALED WITH FIRE STOPPING AND MAINTAIN A MINIMUM OF 2-HOUR, SMOKE TIGHT. IN CASES WHERE ACTUAL RATING IS OTHER THAN 2-HOUR, FIRESTOPPING SHALL MATCH THE EXISTING RATING. ALL PARTITIONS IN WHICH DOORS ARE HELD OPEN SHALL BE CONSIDERED 2-HOUR RATED PARTITIONS. CB1

J. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PATCHING AND PAINTING RESULTING FROM REMOVED DEVICES.

K. NOT USED.

L. NOT USED.

M. NOT USED.

N. WIRELESS NURSE CALL SYSTEM INDICATED ON THE PLANS SHALL BE PROVIDED AND INSTALLED BY THE OWNER. EC SHALL PROVIDE ALL ROUGH-IN AND 120V ELECTRICAL CONNECTIONS REQUIRED FOR A COMPLETE AND OPERATIONAL SYSTEM. CB1

KEYNOTES

1. OWNER PROVIDED AND INSTALLED WIRELESS NURSE CALL REPEATER. OWNER SHALL PROVIDE 10FT CABLE LOOP AT EACH END TO ALLOW FOR FUTURE ADJUSTMENTS. COORDINATE ALL INSTALLATION REQUIREMENTS WITH OWNER'S APPROVED VENDOR. CB1
2. EC SHALL PROVIDE 1-GANG, RECESSED, 3-1/4"D, PVC (NON-METALLIC) BACKBOX WITH WATERPROOF GASKET, MOUNTED AT 42" AFF FOR NURSE CALL SYSTEM PULL CORD STATIONS. (TYPICAL AT EACH NURSE CALL PULL CORD LOCATION). NURSE ALL SYSTEM AND ASSOCIATED DEVICES PROVIDED BY OTHERS.
3. THE BOUNDARY OF THIS AREA IDENTIFIES AS AN R3 SUPPORT HOUSING, RESIDENTAL UNIT. NURSE CALL SYSTEM IS NOT REQUIRED WITHIN THIS AREA.

1 FIRST FLOOR SYSTEMS PLAN - AREA A
SCALE 1/8" = 1'-0"



KEY PLAN

Hoffman
Planning, Design & Construction, Inc.
800.236.2370 | hoffman.net

CONSULTANT:

RING & DUCHATEAU
LIGHTING DESIGN
17400 West Capitol Drive • Brookfield, WI 53045
3575 Cahuenga Blvd. West • Los Angeles, CA 90068
Phone 414.778.1787 | Fax 414.778.2990 | rdl@rngdu.com
RD Project Number: 22338.00

LA CROSSE COUNTY:
HILLVIEW HEALTH CENTER REMODEL
3501 PARK LANE DRIVE, LA CROSSE, WI. 54601

CB1	08/27/2024
AD1	07/08/2024
MARK	DATE
ISSUED:	07/02/2024
PROJECT NO:	23470
DRAWN BY:	VAD
CHECKED BY:	VAD

COPYRIGHT © 2024
HOFFMAN PLANNING, DESIGN & CONSTRUCTION, INC.

FIRST FLOOR SYSTEMS PLAN - AREA A

E-221A